BUILDINGS DIVISION.

Notification dated 18th March 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 7th April 1938, for constructing kitchen for the University Union, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Buildings Division between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing kitchen for the University Union, Bangalore," in default of which tenders wil be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing Kitchen for the Universtiy Union, Bangalore.

Item No.	Description of work	No.	Rate	Contents	Rate to be quoted
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement with watering and tamping, etc.	C.yd.	0 3 0	74	
2	Burnt stone in clay, new, with bond stones at 6 ft. apart	C.ft.	0 3 0	1,917	
3	Old stone in clay with carting	,,	0 2 0	639	
4	Burnt stone slabs, new, one line dressed and fixed in mortar	S.ft.	0 4 6	33	
5	Burnt stone slabs, old, carting, dressing and fixing	S.ft.	0 3 6	33	
6	Burnt stone slabs, new, for pillars and sides dressed and fixed	S.ft.	0 8 0	44	
7	Burnt stone slabs, old, with carting	,,	0 4 0	33	
8	Cutting grooves in pillars	Each	0 8 0	7	
9	Burnt brick in clay, new	C.ft.	0 3 0	2,152	
10	Old brick in clay by carting	,,	0 2 0	714	
11	Teakwood doors with $3\frac{1}{2}'' \times 4\frac{1}{2}''$ frame and panelled shutters and iron fittings, complete	S.ft.	1 6 0	90	
12	Teakwood old doors carting, repairing and fixing	,,	0 4 0	90	
13	Teakwood windows with iron bars $3\frac{1}{2}''$ and $4\frac{1}{2}''$ frame and 4 glazed shutters with iron fittings, etc., complete	S.ft.	1 8 0	120	
14	Teakwood windows, old, with carting, repairing and fixing	S.ft.	0 4 0	60	

Item No.	Description of work	No.	Rate	Contents	Rate to be quoted
			Rs. a. p.		Rs.
15	Teakwood ventilators	S.ft.	0 10 0	96	
16	Carting old trusses from old buildings and fixing	Each	10 0 0	4	
17	Purchasing and fixing steel girders	Cwts.	13 0 0	17½	
18	Teakwood wrought and put up (Mysore teak)	C.ft.	4 8 0	85	
19	Carting old wood with cutting, plaining and fixing	,,	2 0 0	42	
20	Roofing with 1st class mangalore tiles on teak reepers including fixing	Sqr.	22 0 0	12.20	
21	Roofing with old tiles and reepers with carting and fixing	,,	8 0 0	6.00	
22	Providing new ridge tiles and cement pointing	R.ft.	0 8 0	71	
23	Fixing old ridge tiles including cement pointing	,,	0 3 0	35	
24	Providing new teakwood eave-board	R.ft.	0 8 0	136	
25	Providing teakwood finials and pendents	Each	1 8 0	6	
26	R. C. roofing with 2 courses of flat tiles and top and bottom plastering, etc., complete	Sqr.	75 0 0	5.40	
27	Plain cornice with brick work including plastering	R.ft.	0 4 0	72	
28	Plain parapet wall including plastering, etc., complete (2′ high)	R.ft.	1 0 0	72	
29	Mortar plastering	Sqr.	3 0 0	47.70	
30	Flooring with cement concrete of 1½″ over 3″ of lime mortar concrete finished with red oxide etc., complete	,,	22 0 0	13.60	
31	Wax polishing to flooring	,,	3 0 0	13.60	
32	Lac Factory green painting	,,	4 8 0	12.00	
33	Wood oiling, etc.	,,	2 0 0	9.10	
34	Preparing and fixing teak wood wall almirahs with wire gauge shutters	S.ft.	1 0 0	108	
35	Teakwood planks for shelves	,,	0 10 0	78	
36	Teakwood shelf pegs fixed in the wall	Each	1 0 0	24	
37	Supplying, fixing new teakwood trellies	S.ft.	0 12 0	300	
38	Supplying new teakwood reepers 2″×1″ plained ready for fixing roofing	100R.ft.	4 8 0	1,000	
39	Lime mortar concrete of granite jelly	C.ft.	0 3 0	400	

B. R. GARUDACHAR,
Executive Engineer.

BANGALORE DIVISION

Abstract Notification dated 10th March 1938.

The attention of the public is hereby invited to the detailed Notification inviting tenders for improving the Industrial School at Chennapatna published on pages 381-386, Part VI of the *Mysore Gazette* dated 17th March 1938. The last date for the receipt of the tender is 2 P.M. on 4th April 1938 and the tender should accompany with a duplicate challan for having credited the deposit amount of Rs. 440 into the Treasury under 17. (*a*) P. W. Deposits.

Notification dated 16th March 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P. M. on 4th April 1938, for widening and deepening the existing well in the silk farm at Chennapatna. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.